

EL PASO WATER UTILITIES – PUBLIC SERVICE BOARD

ADDENDUM NO. 2

FOR

ZARAGOZA WATER AND SEWER IMPROVEMENTS

BID No. 52-22

October 27, 2022

In accordance with the Instructions to Bidders of the Contract Documents, the following revision to the Plans and/or Specifications shall become part of the Contract Documents and the Bidders shall acknowledge receipt on their Bid Proposal.

EL PASO WATER UTILITIES

ENGINEER OF RECORD



Mirtha Solis
Senior Purchasing Agent*
October 27, 2022



Steven T. Morgan, P.E., TBPE 65340
Project Manager
H₂O Terra, LLC - Firm No. 2103
October 26, 2022

*The Administrator's signature certifies only that this document shall become part of the Contract Documents for the referenced project. His signature is not a representation that the content of this document is technically correct.



RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED IN WRITING AS REQUIRED BY THE BID DOCUMENTS

ANSWERS TO SUBMITTED QUESTIONS

- Q1. Bid Item #6 Bid Schd calls out for 2,349 LF plans show 2240 LF please verify.
A. See the revised Section 00300 – Bid Form.
- Q2. Bid Item #7 Bid Schd calls out for 395 LF plans show 500 LF please verify.
A. See the revised Section 00300 – Bid Form.
- Q3. Bid Item #12 Bid Schd calls out for 22 EA plans show 25 EA please verify.
A. See the revised Section 00300 – Bid Form.
- Q4. Bid Item #13 Bid Schd calls out for 605 LF plans show 700 LF please verify.
A. See the revised Section 00300 – Bid Form.

VOLUME 1 – AGREEMENT AND SPECIFICATIONS

AD-2.1 SECTION 00010 – INFORMAL NOTICE | SECTION 00020 - INVITATION TO BID |
00500 - STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR |
SECTION 01 11 00 - SUMMARY OF WORK | SECTION 01 22 13 - MEASUREMENT
AND PAYMENT

- A. In each of the sections specified above, after the **Scope of the Summary of Work** is briefly described below” **DELETE** Items (4), (5), (6) and (14) in their ENTIRETY and **REPLACE** with the following:
4. Furnish and install approximately 2,244 linear feet (lf) of 8-inch Sanitary Sewer line; approximately; and 13 Type A Manholes and 24 additional vertical feet.
 5. Furnish and install 26 sanitary sewer service connections with approximately 740 lf of 4-inch sewer main for connection to the new 8-inch Sanitary Sewer line.
 6. Clean, Video and Test approximately 2,729 lf of 8-inch Sanitary Sewer line and 740 lf of 4-inch sanitary sewer service laterals.
 14. Remove and dispose of 1,261 lf of 8-inch sewer main.

AD-2.2 SECTION 00300 – BID FORM

- A. PAGES 3, 4, 5 BID FORM – **DELETE** Pages 3, 4, 5 in its ENTIRETY and **REPLACE** with the attached “ADDENDUM NO. 2 – SECTION 00300 BID FORM PAGES 00300-3, 00300-4 and 00300-5” for the bid package submittal.

AD-2.3 SECTION 01 22 13 – MEASUREMENT AND PAYMENT ITEM (V) BID ITEM 25 – REMOVE AND DISPOSE OF 8-INCH SANITARY SEWER

DELETE the two Measurement and Payment Paragraphs in their ENTIRETY and **REPLACE** with the following:

Measurement for the removal and disposal of the 8-inch sanitary sewer line shall be measured along the centerline of the line removed and disposed complete in place.

Payment will be made at the stated unit price per linear foot removed and disposed and accepted by the Owner or Engineer as being fully removed and disposed. Payment shall be full compensation for all material, equipment and labor required per linear foot for the complete removal and disposal and all incidentals.

Payment for all associated excavation and for installation of the new 8-inch sewer main will be made at the stated unit price per linear foot for Bid Item No. 6 or 7 as specified, to include excavation, backfill, compacting, testing and any other requirements.

VOLUME 2 – DRAWINGS

AD-2.4 DRAWING C6 (SHEET 9 OF 18) *N. ZARAGOZA RD. DECOMMISSIONING & REMOVE AND DISPOSE OF EXISTING 8-INCH SEWER LINE PLAN AND PROFILE STA 1+00 TO STA 10+00*

- A. **DELETE** KEYED NOTE ③ IN ITS ENTIRETY THAT READS “EXISTING MANHOLES TO ALLOW FOR INSTALLATION OF NEW SEWER MAIN”
- B. MH STA 3+49 and MH STA 5+51 **DELETE** reference to KEYED NOTE ③ and **REPLACE** with reference to KEYED NOTE ④ “DECOMMISSION EXISTING MANHOLES SEE DETAIL SHEET C15”.
- C. STA 1+00 to STA 8+50 **DELETE PLAN NOTE** that reads “Remove and Replace Existing 8-inch Sewer Line” and **REPLACE WITH KEYED NOTE ⑤** that reads “8-inch Sanitary Sewer Line shall be decommissioned by pumping a 2-sack sand cement slurry into the line.”

ATTACHMENTS

ATTACHMENT NO. 1 – SECTION 00300 BID FORM PAGES 00300-3, 00300-4 and 00300-5.

Addendum No. 1, pages 1 through 4 and ATTACHMENT NO. 1 (pages 00300-3, 00300,4, and 00300-5) shall become part of the Contract and all provisions of the Contract shall apply thereto. The time provided for the completion of the Contract is not changed. Bidders shall acknowledge receipt of all Addenda by number in the space provided in the Proposal.

****END OF ADDENDUM NO. 2 ****

ADDENDUM NO. 2 – ATTACHMENT NO. 1
SECTION 00300 - BID FORM

***** HIGH IMPORTANCE *****

TEXAS ETHICS COMMISSION REQUIREMENT

*****IN THE EVENT YOU RECEIVE AN AWARD OF THIS CONTRACT*****

Reference: FORM 1295 (revised 12/22/17) "Certificate of Interested Parties"

**A business entity must file Form 1295 electronically with the Texas Ethics Commission using the Commission's online filing application, which can be found at:
https://www.ethics.state.tx.us/whatsnew/elf_info_form1295.htm**

SEE INSTRUCTIONS: Form 1295 and Sample Form 1295 (Section 00302)

Item No.	Estimated Quantity	UOM	Description	Unit Bid Price	Extended Amount (Qty x Unit Price)
1.	1	LS	Insurance, Bonds, and move-In Related Expenses, Not to Exceed 5% of Bid Item Nos. 2 through 30.	\$ _____	\$ _____
2.	1	LS	Provide TPDES Stormwater Pollution Prevention Plan for the Project, complete.	\$ _____	\$ _____
3.	1	LS	Provide Traffic Control complete with devices and traffic safety system, complete for all of the project in place as required in compliance with the City of El Paso	\$ _____	\$ _____
4.	1	LS	Videotaping and photographic documentation of the project area before and after construction, complete; not to exceed \$1.00 per linear foot of pipe to be installed.	\$ _____	\$ _____
5.	3,156	LF	Trench Safety System all 8-inch line (Water and Sewer): Trench Box Method or Shoring, Sheeting and Bracing Method.	\$ _____	\$ _____
6.	2,244	LF	Furnish and install new 8-inch sanitary sewer pipe (PVC SDR 35) and fittings, as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____
7.	485	LF	Furnish and install new 8-inch sanitary sewer pipe (C900) and fittings, as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____
8.	2,729	LF	Clean, Video, and Test new 8-inch sanitary sewer pipe and manholes, complete.	\$ _____	\$ _____
9.	1	EA	Line A Tie-in to existing 8-inch Sanitary sewer line on Roseway (Sta 1+00), as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____

ADDENDUM NO. 2 – ATTACHMENT NO. 1
SECTION 00300 - BID FORM

10.	1	EA	Line B Tie-in to existing 8-inch Sanitary sewer line on Billy the Kid (Sta 1+00), as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____
11.	1	EA	Line E Tie-in to existing 8-inch Sanitary sewer line on Zaragoza (Sta 4+94), as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____
12.	26	EA	Furnish and Install new 4-inch service connections as detailed in the drawings and as specified, complete in place.	\$ _____	\$ _____
13.	740	LF	Install, 4-inch New SDR 35 sewer service lines, as detailed in the drawings and as specified, complete in place.	\$ _____	\$ _____
14.	740	LF	Clean, test, and video 4-inch PVC sewer service lines, complete in place	\$ _____	\$ _____
15.	1	EA	Plug 2 existing 8-inch sanitary sewer lines as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____
16.	13	EA	Furnish and install new sanitary sewer manhole (Type A), complete in place.	\$ _____	\$ _____
17.	24	VF	Furnish and Install Vertical Manhole (above 6'), complete in place.	\$ _____	\$ _____
18.	427	LF	Furnish and install new 8-inch C-900 water line using open cut and fittings as detailed in the drawings and as specified, complete in place	\$ _____	\$ _____
19.	2	EA	Furnish and Install 8-inch tapping sleeves and valves as detailed in the drawings and as specified, complete in place.	\$ _____	\$ _____
20.	427	LF	Clean, and Test new 8-inch C-900 water line, complete.	\$ _____	\$ _____
21.	8,300	SY	Remove, dispose and replace existing HMAc, as specified, complete in place.	\$ _____	\$ _____
22.	2	EA	Decommission 4 feet diameter manholes as detailed in the drawings and as specified complete in place.	\$ _____	\$ _____
23.	7	EA	Remove and dispose 4-feet diameter manholes as detailed in the drawings and as specified complete in place.	\$ _____	\$ _____
24.	915	LF	Decommission 8-inch Sanitary Sewer Lines as detailed in the drawings and as specified complete in place.	\$ _____	\$ _____
25.	1,261	LF	Remove and dispose 8-inch Sanitary Sewer Lines as detailed in the drawings and as specified complete in place.	\$ _____	\$ _____

ADDENDUM NO. 2 – ATTACHMENT NO. 1
SECTION 00300 - BID FORM

26.	1,000	CY	2 Sack Backfill for within City of El Paso, ROW as specified, complete in place.	\$ _____	\$ _____
27.	64	SF	Remove and replace concrete drive -way, complete in place	\$ _____	\$ _____
28.	1,400	SF	Remove, dispose and replace sidewalk, complete in place	\$ _____	\$ _____
29.	1	LS	Furnish, install, operate and maintain, bypass pumping operations, complete in place	\$ _____	\$ _____
30.	224	LF	Remove and replace concrete curb & gutter	\$ _____	\$ _____

TOTAL BID PRICE (ITEMS 1 THROUGH 30) \$ _____

Quantities are not guaranteed.

If multiple awards are contemplated under a single bid document, an additional breakdown of bid amounts, subcontractors, and suppliers is required. It will also be necessary to adjust the MWBE Certification and Participation Summary Form accordingly.

In accordance with Section 151.311 of the Texas Tax Code (V.A.T.C.S.), regarding taxes on materials and services, and requiring a separated contract, the following is the breakdown of cost for materials and cost for labor for this bid:

MATERIALS TO BE INCORPORATED IN PROJECT NOT SUBJECT TO SALES TAX: \$ _____

LABOR TO BE INCORPORATED IN PROJECT NOT SUBJECT TO SALES TAX: \$ _____

RENTAL EQUIPMENT AND OTHER TAXABLE ITEMS: \$ _____

OTHER (I.E. BONDS, INSURANCE, CAPITAL EQUIPMENT, ETC.) \$ _____

***TOTAL CONTRACT:** \$ _____
***(TOTAL MUST EQUAL TOTAL BID PRICE)**

5. BIDDER agrees that the Work will be Substantially completed within **180** Calendar Days from the date when the Contract Time commences to run as provided in Paragraph 2.03 of the General Conditions, and as revised in Supplementary Conditions, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions, and as revised in the Supplementary Conditions, within **210** calendar days. Final completion includes CONTRACTOR’S resolution of all punch list items and CONTRACTOR’S submission of required close-out documentation. Any failure of the CONTRACTOR to complete the project within the contract time will be considered a material breach of this contract.

BIDDER accepts the provisions of the Supplementary Conditions and the Agreement as to liquidated damages in the event of failure to complete the Work on time.